



REPUBLIC OF KENYA
MINISTRY OF AGRICULTURE AND LIVESTOCK DEVELOPMENT
STATE DEPARTMENT FOR AGRICULTURE
BUILDING RESILIENCE FOR FOOD AND NUTRITION SECURITY IN THE HORN OF
AFRICA (BREFONS)

Telegraphic Address "MINAG" NAIROBI
Telephone: 2215704/8/9 Ext. 1139
Fax: (020)2244337
When replying Please Quote

HILL PLAZA
9th Floor
Cathedral Road
P.O. Box 30028-00100
NAIROBI
4th January, 2024

RE: ADDENDUM NO.4

INCLUSION OF MISSING ELEMENT NO.02- SUPERSTRUCTURE UNDER BILL NO.02 -
HAY SHED IN THE FOLLOWING TENDERS:

1. TENDER NO. MOALD/BREFONS/T032/2023-2024 - CONSTRUCTION OF KISERIAN HAY SHED IN BARINGO COUNTY
2. TENDER NO. MOALD/BREFONS/T034/2023-2024 - CONSTRUCTION OF CHEPKALACH HAY SHED IN BARINGO COUNTY
3. TENDER NO. MOALD/BREFONS/T036/2023-2024 - CONSTRUCTION OF KIMOSE HAY SHED IN BARINGO COUNTY
4. MOALD/BREFONS/T009/2023-2024- CONSTRUCTION OF LESIRIKAN HAY SHED IN SAMBURU COUNTY
5. MOALD/BREFONS/T010/2023-2024- CONSTRUCTION OF TUUM HAY SHED IN SAMBURU COUNTY
6. **MOALD/BREFONS/T014/2023-2024**- CONSTRUCTION OF WALDA HAY SHED IN MARSABIT COUNTY
7. **MOALD/BREFONS/T015/2023-2024**- CONSTRUCTION OF SOLOLO HAY SHED IN MARSABIT COUNTY
8. MOALD/BREFONS/T016/2023-2024- CONSTRUCTION OF LOGLOGO HAY SHED IN MARSABIT COUNTY

Pursuant to section 75 of the Public Procurement and Asset Disposal Act, 2015, Element No.02-Superstructure under Bill No.02-Hay Shed is missing and has been included in each of the above tender documents as indicated below.

| ITEM | DESCRIPTION | UNIT | QTY | RATE KSHS | AMOUNT | |
|------|---|------|-----|--------------|--------|-----|
| | | | | | KSHS | CTS |
| | <u>BILL NO. 02</u> | | | | | |
| | <u>HAY SHED</u> | | | | | |
| | <u>ELEMENT NO.02</u> | | | | | |
| | <u>SUPERSTRUCTURE</u> | | | | | |
| | <u>mild Steel to B.S. 449</u> | | | | | |
| A | 114 mm Diameter tube column 3mm thick (Length 5000mm spaced at 3 m c/c with welded 5 Y12 bars at appropriate position for casting in RC | NO | 26 | | | |
| B | 100x100 x4.0mm Rectangular Hollow Section with welded connections. | LM | 78 | | | |
| C. | 50x50x4.0mm Square Hollow Section with welded connections fixed with bolts | LM | 550 | | | |
| D | 75x75x3.0mm Angle Plate fixed with Bolts. | NO | 170 | | | |
| | | | 0 | | | |
| E. | 200X200X4mm Bottom end plate | NO | 26 | | | |
| F | 300X200X4mm top plate | NO | 52 | | | |
| | <u>Reinforcement</u> | | 0 | | | |
| | <u>High Tensile Steel Reinforcement to B.S. 4483</u> | | 0 | | | |
| G | BRC MESH A98.Weighing 2.22kg per square metre:200mm laps | SM | 350 | | | |
| | TOTAL ELEMENT NO.02 CARRIED TO SUMMARY END OF BILL | | | | | |

DELETION OF REPEATED ELEMENT NO.03-ROOFING AND RAIN WATER DISPOSAL UNDER BILL NO.02- HAY SHED IN THE FOLLOWING TENDERS:

1. TENDER NO. MOALD/BREFONS/T032/2023-2024 - CONSTRUCTION OF KISERIAN HAY SHED IN BARINGO COUNTY
2. TENDER NO. MOALD/BREFONS/T034/2023-2024 - CONSTRUCTION OF CHEPKALACH HAY SHED IN BARINGO COUNTY

3. TENDER NO. MOALD/BREFONS/T036/2023-2024 - CONSTRUCTION OF KIMOSE HAY SHED IN BARINGO COUNTY
4. TENDER NO. MOALD/BREFONS/T039/2023-2024 - CONSTRUCTION OF ONOTO HAY SHED IN BARINGO COUNTY
5. MOALD/BREFONS/T009/2023-2024- CONSTRUCTION OF LESIRIKAN HAY SHED IN SAMBURU COUNTY
6. MOALD/BREFONS/T010/2023-2024- CONSTRUCTION OF TUUM HAY SHED IN SAMBURU COUNTY
7. **MOALD/BREFONS/T014/2023-2024-** CONSTRUCTION OF WALDA HAY SHED IN MARSABIT COUNTY
8. **MOALD/BREFONS/T015/2023-2024-** CONSTRUCTION OF SOLOLO HAY SHED IN MARSABIT COUNTY
9. MOALD/BREFONS/T016/2023-2024- CONSTRUCTION OF LOGLOGO HAY SHED IN MARSABIT COUNTY

Pursuant to section 75 of the Public Procurement and Asset Disposal Act, 2015, Element No.03- Roofing and Rain Water Disposal under Bill No.02-Hay Shed is repeated and one has been deleted from each of the above tender documents as indicated below.

| ITEM | DESCRIPTION | UNIT | QTY | RATE KSHS | AMOUNT | |
|------|---|------|-------|--------------|--------|-----|
| | | | | | KSHS | CTS |
| | <u>BILL NO. 02</u> | | | | | |
| | <u>HAY SHED</u> | | | | | |
| | | | | | | |
| | <u>ELEMENT NO.03</u> | | | | | |
| | <u>ROOFING AND RAINWATER DISPOSAL</u> | | | | | |
| | <u>The following in 10 NO. Roof Trusses spanning 12m and hoisting and building 4 m above the ground</u> | | | | | |
| | <u>Steel Hollow Sections</u> | | | | | |
| A | 50X50mmX3mm Braces, ties, strut, and posts | LM | 190.5 | | | |
| | 75x50mm Rafters | LM | 306 | | | |
| B | 100X100 X 4mm Rafters | LM | 0 | | | |

| | | | | | | |
|---|--|------|------|--|--|--|
| | <u>Galvanized mild steel</u> | | 0 | | | |
| C | 12 mm Diameter Rawl bolt 150mm long with head nut and two washers | NO | 72 | | | |
| D | 175x250x6mm baseplate | NO | 25 | | | |
| | 600x200x6mm plate joining trusses | NO | 20 | | | |
| E | 127x52x19x2mm Z-Purlins sold in 6m lengths | NO | 60 | | | |
| | <u>Wrought Treated Cypress</u> | | | | | |
| F | _200mm x75mm Fascia or barge board | L.M | 99.4 | | | |
| | <u>Galvanized mild steel</u> | | | | | |
| G | 200X200X2mm plate welded to end truss and drilled for 12mm diameter bolt for fixing fascia board | NO | 0 | | | |
| H | 12 mm Diameter bolt 150mm long with head nut and two washers for fixing fascia board | NO | 0 | | | |
| | <u>28 Gauge Roof Covering Corrugated 'Resincot' Iron Sheetting and Accessories as Manufactured by Gal sheet K Ltd or equal and approved</u> | | 0 | | | |
| I | Roofing Covering with 1 ½ Corrugation side laps fixed to steel member Purlins with self-tapping screws (Measured out and allow for laps) | S.M | 456 | | | |
| J | Half Round Ridge Capping | L.M | 31.4 | | | |
| | <u>Rain water Disposal 16mm Galvanized Sheet Metal</u> | | | | | |
| K | 150 mm Diameters in the Half round gutter with dry joints in the running length and fixed to timber fascia with brackets at 900mm centre to centre | L.M. | 62.8 | | | |
| L | Stopped end | NO. | 4 | | | |
| M | Bend | NO. | 10 | | | |
| N | 100mm nozzle outlet | NO. | 2 | | | |
| O | 100mm Diameter down pipe with dry socket joints and fixed to pillar column with brackets | L.M | 25 | | | |

| | | | | | | |
|---|---|-----|---|--|--|--|
| P | Swan neck bend with 600mm projection | NO. | 4 | | | |
| Q | Shoe | NO. | 4 | | | |
| | TOTAL ELEMENT NO.03 CARRIED TO SUMMARY END OF BILL | | | | | |

Take note that all other conditions of the tender document shall remain the same.

Head, Supply Chain Management Unit

For: PRINCIPAL SECRETARY