

PAVING OF MOGOGOSIEK AGGREGATION CENTRE COMPOUND IN KONOIN CONSTITUENCY, BOMET COUNTY (MOALD/SDA/ENG/DAC/06/2024-2025)

ADDITIONAL WORKS FOR PAVING OF MOGOGOSIEK AGGREGATION CENTRE COMPOUND IN KONOIN CONSTITUENCY, BOMET COUNTY (MOALD/SDA/ENG/DAC/06/2024-2025)					
	BILL NO. 3: SUPPLY AND INSTALLATION ROOF WATER HARVESTING, STORAGE AND DISTRIBUTION SYSTEM FOR MOGOGOSIEK GRAIN DRYING AND STORAGE FACILITY				
A	Supply materials and construct 10,000 litres plastic tank bases as per specifications and instruction by Resident Engineer	No	2		
B	Supply, deliver and install vertical close end plastic moulded water tank of capacity 10,000 litre size connected to the Main Store Roof Water Harvesting System. The tank to be assembled complete with cover and having screwed connections for inlet, outlet and overflow, 32mm medium pressure ball valve, drain pipes and any other necessary item for its proper functioning including fittings. The tank shall be mounted on top of the tank base constructed in A above and as approved by the Resident Engineer.	No.	2		
C	Supply, deliver and construct 6m high steel structure to support 5,000 litres plastic tank for gravity distribution of water as per specifications and instruction by Resident Engineer	No	1		
D	Supply, deliver and install vertical close end plastic moulded water tank of capacity 5,000 litre. The tank to be assembled complete with cover and having screwed connections for inlet, outlet and overflow, 32mm medium pressure ball valve, drain pipes and any other necessary item for its proper functioning including fittings. The tank shall be mounted on top of the Elevated Steel Structure (ESS) as approved by the Resident Engineer.	No.	1		
E	Supply and Install small electric booster pump to elevate 5,000 litres plastic tank indicated in D above	No	1		
	TOTAL CARRIED TO GRAND SUMMARY				

PAVING OF MOGOGOSIEK AGGREGATION CENTRE COMPOUND IN KONOIN CONSTITUENCY, BOMET COUNTY (MOALD/SDA/ENG/DAC/06/2024-2025)

Bill of Quantities/Schedules of Prices

Item	Description	Unit	Qty	Rate	Amount Kshs
	<u>BILL NO.4: PROVISIONAL SUMS</u>				
A	Allow a Provisional sum of Kenya Shillings One Million Two Hundred Thousand KShs. 1,200,000.00) for supply and installation of Three Phase Electricity including trunking for Main Store and provision for Mobile Grain Dryer as per instructions by Resident Engineer	LSUM	1		
B	Allow a Provisional sum of Kenya Shillings Six Hundred Thousand (KShs. 600,000.00) for Grading and Murraming Access Road from Tarmac to store as per specifications and instructions by Resident Engineer	LSUM	1		
	TOTAL BILL 4 (PROVISIONAL SUMS) CARRIED TO GRAND SUMMARY				

GRAND SUMMARY FOR PAVING OF MOGOGOSIEK AGGREGATION CENTRE COMPOUND IN KONOIN CONSTITUENCY, BOMET COUNTY

BILL No.	DESCRIPTION	CONTRACT AMOUNT (KES)
Bill No. 1	Preliminary and General Works	
Bill No. 2	Cabro Pavements	
Bill No. 3	Supply and installation roof water harvesting, storage and distribution system	
Bill No. 4	Provisional Sums	
	SUB-TOTAL 1	
	ADD 10% CONTINGENCIES	
	SUB-TOTAL 2	
	ADD 16% VAT	
	TOTAL	